

City of El Paso - City Plan Commission Staff Report

Case No: SUSU16-00018 Painted Desert at Mission Ridge 1

Application Type: Major Combination **CPC Hearing Date:** May 19, 2016

Staff Planner: Armida Martinez, (915) 212-1605, martinezar@elpasotexas.gov

Location: West of Darrington and North of Paseo Del Este

Acreage: 50.468 Rep District: ETJ

Existing Use:VacantExisting Zoning:ETJProposed Zoning:ETJ

Nearest Park: 4.575 acre park proposed within the subdivision

Nearest School: Dr. Sue Shook Elementary (.25 miles)

Park Fees Required: N/A Impact Fee Area: N/A

Property Owner: Hunt Mission Ridge, LLC. **Applicant:** Hunt Mission Ridge, LLC.

Representative: CEA Group

SURROUNDING ZONING AND LAND USE

North: ETJ / vacant South: ETJ / Vacant East: ETJ / vacant West: ETJ / Vacant

PLAN EL PASO DESIGNATION: G4, Suburban (Walkable)

APPLICATION DESCRIPTION

The applicant proposes to subdivide 50.468 acres. Access to the subdivision will be from Darrington Road and Paseo Del Este Boulevard. The proposed development is for 142 single family lots ranging between 4,692 and 12,727 square feet, a 13.804 acre commercial lot, a 4.575 acre park, and a 1.701 storm water pond. The property has been granted vested rights under the previous subdivision code.

SUSU16-00018 1 May 19, 2016

The applicant is requesting the following modifications:

- 1. To allow a 54 ft. roadway cross-section with two 17 foot paved driving lanes with 6 inch curb and gutter on both sides of the roadway, two 5 foot parkways abutting the curb and two 5 foot concrete sidewalks for the proposed local streets.
- 2. To allow 54ft. roadway cross –section with two17 foot paved driving lanes with 6 inch curb and gutter both sides of the roadway, one 5 foot concrete sidewalk, one 5 foot parkway abutting the sidewalk, and one 10 foot hike and bike trail for Stamfordham Street.
- 3. To allow a modified 66 foot roadway cross-section with two 20 foot paved driving lanes with 6 inch curb and gutter on both sides of the roadway, a raised 6 foot landscaped median, two 5 foot concrete sidewalks, and two 5 foot parkways abutting the sidewalks for Kilvington and Harbottle Streets.

The County of El Paso granted the applicant ROW variances on January 13, 2014 to allow the proposed cross-sections.

CASE HISTORY

Painted Desert at Mission Ridge 1 was approved by the City Plan Commission on a major preliminary basis along with the currently proposed modifications on July 17, 2014.

DEVELOPMENT COORDINATING COMMITTEE

The Development Coordinating Committee recommends **approval** of the modifications request and **approval** of Painted Desert at Mission Ridge 1 Subdivision on a Major Combination basis subject to the following conditions and requirements:

• That the City Plan Commission require the applicant to landscape the parkway area on all double frontage lots as stipulated under Section 19.16.080.D of the previous code.

D. The city plan commission may require that a parkway at the rear of a double frontage lot be landscaped or other aesthetic treatment be provided by the subdivider, subject to the approval of the planning & economic development director or designee, to provide visual separation between the development and the street.

Planning Division Recommendation:

Staff recommends **approval** of the modification request as per Section 19.04.170.A3 of the previous subdivision code and **approval** of Painted Desert at Mission Ridge 1 Subdivision.

19.04.170.A3. The subdivider has demonstrated an alternative method of development that will improve the aesthetic value of the subdivision while giving equal emphasis to safety, economy, tax yield, maintenance cost, response time, drainage, dedication of parkland and open space amenities and vehicular access and pedestrian passage.

<u>Planning & Inspections Department - Land Development</u>

We have reviewed subject plats and recommend Approval.

The Developer/Engineer shall address the following comments.

- 1. As per section Code 18.08.010, section D, all drainage structures and ponding areas serving the subdivision are constructed as part of the initial phase of the development.
- 2. All storm water management facilities from Unit 2 should be in place concurrently with development of the subject subdivision.
- 3. The developer shall be responsible for maintenance of all offsite storm-water management facilities unless drainage easements or rights-of-way with adequate access are provided; label drainage systems within Lot 18, between Lots 5 & 6 in Block 6 and whether they are public or private on the final plat.
- 4. Verify if runoff from commercial Lot 18 Block 6 is designated for just the one pond and system or for both ponds and systems since inlets from both ponds are being provided. Verify if design capacities are adequate.
- 5. At the improvement plan stage, protect the subject property from stormwater runoff from the adjacent terrain.

Parks and Recreation Department

We have reviewed <u>Painted Desert at Mission Ridge 1</u>, a major combination plat map which is composed of <u>142</u> Single-family residential dwelling lots and includes a <u>4.57 Acre</u> "Park / Pond" and <u>13.80 acres</u> for commercial purposes therefore on behalf of CID Parks Planning Division we offer Developer / Engineer the following comments:

1. For informational purposes, the subdivision improvement plans shall also include the improvement plans for the proposed "Park / Pond" area.

Per City standards a total of 1.42 acres of "Parkland" and "Park fees" in the amount of \$13,800.00 for the commercial parcel would have been required however,

This subdivision is excluded from the calculation for "Parkland Dedication" as **it is not** identified on the official map as described per ordinance Title 19 – Subdivision & Development Plats, **Chapter 19.20 - Parks & Open Space** as noted below.

Section 19.20.020 - Dedication Required

A. Dedication Required. All subdivisions located within the corporate limits of the City of El Paso and within those areas designated in the City's extra territorial jurisdiction (ETJ), as identified on an official map kept in the Development Services Department.

El Paso Water Utilities

1. EPWU does not object to this request.

General

2. The proposed subdivision is located within the East El Paso Extraterritorial Jurisdiction (ETJ) within one of the Paseo Del Este Municipal Utility Districts (MUDs) service area. The Paseo Del Este MUD receives wholesale water and wastewater service from the El Paso Water Utilities – Public Service Board (EPWU-PSB) in accordance with the Paseo del Este Wholesale Contract and EPWU-PSB Rules and Regulations No. 11.

El Paso Electric Company

No comments received.

El Paso Fire Department

No comments received.

Central Appraisal District

No objections.

Texas Gas Company


No comments received.


Additional Requirements and General Comments:


- 1. Submit to the Planning & Inspections Department Planning Division the following prior to recording of the subdivision.
 - a. Current certified tax certificate(s)
 - b. Current proof of ownership
 - c. Release of access document, if applicable
 - d. Set of restrictive covenants, if applicable
- 2. Every subdivision shall provide for postal delivery service. The subdivider shall coordinate the installation and construction with the United States Postal Service in determining the type of delivery service for the proposed subdivision. In all cases, the type and location of delivery service shall be subject to the approval of the United States Postal Service.

Attachments


- 1. Location map
- 2. Aerial map
- 3. Preliminary plat
- 4. Final Plat
- 5. Cross-Sections
- 6. Waiver Request
- 7. Application













Castner Center @ Transmountain 4712 Woodrow Bean, Ste. F El Paso, TX 79924 Office: 915.544.5232 Fax: 915.544.5233 web: www.ceagroup.net

April 19, 2016

City of El Paso-Planning & Inspections Development 801 Texas Ave. El Paso, Texas 79901

Attention:

Mr. Alfredo Austin,

Planner

Reference:

Painted Desert at Mission Ridge 1, Major Combination Plat Approval -

Modification Letter

Dear Mr. Austin:

On behalf of the Developer for the above referenced development, we are requesting modifications to the subdivision regulations. These modifications will include the following adjustments:

Modification No. 1: 54 foot Roadway

This modification shall consist of a 54 foot roadway cross-sections with 2- 17 foot paved driving lanes with 6-inch curb and gutter on both sides of the roadway, 2- 5 foot parkways abutting the curb and 2- 5 foot concrete sidewalks.

Modification No. 2: 54 foot Roadway

This modification shall consist of a 54 foot roadway cross-section with 2- 17 foot paved driving lanes with 6-inch curb and gutter on both sides of the roadway, 1- 5 foot concrete sidewalk, 1- 5 foot parkway abutting the sidewalk, and 1- 10 foot hike and bike trail.

Modification No. 3: 66 foot Roadway

This modification shall consist of a 66 foot roadway cross-section with 2- 20 foot paved driving lanes with 6-inch curb and gutter on both sides of the roadway, a raised 6-foot landscaped median, 2- 5 foot concrete sidewalks, and 2- 5 foot parkways abutting the sidewalks.

If you have any questions regarding this issue, please do not hesitate to call me at office number 915.544.5232. We thank you for your cooperation on this issue and look forward to your favorable consideration to our request.

Sincerely, CEA Group

derge Grajeda, P.E.

Project Manager

engineers • architects • planners



CITY PLAN COMMISSION APPLICATION FOR MAJOR COMBINATION SUBDIVISION APPROVAL

		10.0		-		
Property Land Uses:						
611611	ACRES SITES		_	ACRES	SITE	
Single-family	18.409 142		Tice			
Duplex			reet & Alley	11.979	13	
Apartment Mobile Home			nding & Drainage	1.701	1_	
P.U.D.			stitutional			
P.U.D. Park	4.575 1	Ot	her (specify below)			
rurk School	4.075	_				
Commercial	13.804 1	<u></u>	. 137. 00			
Industrial	13.00		tal No. Sites	158		
midu50 iai		10	tal (Gross) Acreage_!	50.468	-	
existing residential 20		No				
What type of utility ea	asements are proposed: Ur	derground	Overhead Co	ombination of Bo	th_x_	
What type of drainage is proposed? (If applicable, list more than one) Storm water run-off will be conveyed via sheet flow to proposed atorm drainage infrastructure that will ultimately discharge to an on-site retention basin						
Are special public imp	provements proposed in cor	nection with dev	relopment? Yes	No	x	
Is a modification or ex	ception of any portion of the	e Subdivision O	rdinance proportion	Van v	Ma	
If answer is "Yes". ple	ease explain the nature of the	e modification o	r exception 54-ft row	st. with (2) 5-8 et	140	
(2) 5-ft parkways, (2) 1	7-ft lanes and 66-ft row st. v	vith (2) 5-ft parkw	ays, (2) 5-fl sidewalks	(2) 20-ft lanes (1) 6-ft n	
Remarks and/or expla	nation of special circumstar	ces: Approved o	county variances.			
			-	- ₹0	_	
mprovement Plan	s submitted? Ye	xNo				
	s submitted? Ye					

City Development Department 811 Texas | P.O. Box 1890 | El Paso, Texas 79950-1890| (915) 212-0085

12.	Owner of recor	d Hunt Mission Ridge, LL	C 4401 N. Mesa	79902	(915) 533-1122
		(Name & Address)		(Zip)	(Phone)
13.	Developer	Same as owner		XXI: XX - XX	
		(Name & Address)		(Zip)	(Phone)
14.	Engineer	CEA Group	4712 Woodrow Bean, Suite F	79924	(915) 544-5232 .
		(Name & Address)		HWENN A	Ston Rope
		tember 1, 2014, a 3%	OWNER SIGNATURE:	1	ar
	Technology fee has been added to all Planning application fees.		REPRESENTATIVE	1	0

NOTE: SUBMITTAL OF AN APPLICATION DOES NOT CONSTITUTE ACCEPTANCE FOR PROCESSING UNTIL THE PLANNING DEPARTMENT REVIEWS THE APPLICATION FOR ACCURACY AND COMPLETENESS.

City Development Department 811 Texas | P.O. Box 1890 | El Paso, Texas 79950-1890| (915) 212-0085